



EARTHWORK		
COLOR	CUT(-) / FILL(+)	AREA (SF)
Blue	-30' to -12'	33,168
Cyan	-12' to -6'	49,773
Green	-6' to 0'	226,778
Yellow	0' to +6'	153,391
Red	+6' to +12'	60,196
Purple	+12' to +27'	10,055

PARK SITE EARTHWORK QUANTITY	
CUT	57,223 CY
FILL	36,559 CY
EXPORT	20,664 CY
*EXPANSION INDEX = 0	


URBAN RESOURCE
 CONSULTING CIVIL ENGINEERS

23 MAUCHLY, SUITE 110
 IRVINE, CA 92618
 PHONE: 949-727-9095
 FAX: 949-727-9098

**SUNSET RIDGE PARK
 EARTHWORKS EXHIBIT**

DECEMBER 15, 2011